






Minerals and Waste Joint Plan



Addendum of Proposed Changes to Publication Draft

July 2017

Introduction

- 1. As planning authorities for minerals and waste in each of their areas, North Yorkshire County Council, City of York Council and the North York Moors National Park Authority have a responsibility to take decisions on planning applications for related development. The three Authorities, (referred to as 'the Authorities'), also have a duty to produce planning policies to help to take those decisions.
- 2. The Authorities have worked jointly to prepare a Minerals and Waste Joint Plan, referred to as the 'Joint Plan', containing planning policies to help us to take decisions about matters such as where, when and how minerals and waste developments should be planned and controlled up to 31 December 2030.
- 3. Work commenced on the Joint Plan in May 2013, with further rounds of consultation taking place through an Issues and Options consultation in February 2014, followed by a Supplementary Sites consultation in January 2015 and a Preferred Options consultation in November 2015. After considering all the responses received at all stages, together with other available evidence, the Publication Draft Plan and Policies Map were published, in accordance with regulation 19 of the Town and Country Planning (Local Planning) (England) Regulations 2012, to provide an opportunity for representations to be made regarding legal compliance and the 'soundness' of the Joint Plan, before it is submitted for examination in public by an independent planning inspector.
- 4. The Joint Plan was made available for a period of representations for six weeks from 9th November to 21st December 2016. Representations received at this stage have been assessed and as a result a number of amendments to the Plan are being proposed.
- 5. This **Addendum of Proposed Changes** is being provided as an opportunity to consider, and make comments on the proposed amendments before the Publication Draft Plan is submitted, along with the other submission documents including the Addendum, for examination in public.
- 6. The Addendum clearly indicates the proposed change and the corresponding part of the Publication Draft Plan that would be amended The Publication Draft Plan and supporting documents are available to view at www.northyorks.gov.uk/mwjointplan. The Addendum of Proposed Changes, and any submitted representations, will be reviewed by the planning inspector during the examination in public.
- 7. Representations can be made over an eight week period on matters of soundness and legal compliance with relevant legislation.

Explanation of the Proposed Changes

- 8. This **Addendum of Proposed Changes** is being provided as an opportunity to consider, and make comments on the proposed amendments before the Publication Draft Plan is submitted, along with the other submission documents including the Addendum, for examination in public.
- 9. The Addendum clearly indicates the proposed change and the corresponding part of the Publication Draft Plan that would be amended. The Addendum of Proposed Changes, and any submitted representations, will be reviewed by the planning inspector during the examination in public.

- 10. It is recognised that many of the proposed changes are technical in nature and it may not be immediately obvious what this change means in terms of applying the policies to planning applications in the future.
- 11. A brief summary and explanation of the proposed changes on a topic basis is provided below to assist you. The acronym PC and a numbered suffix refers to a specific proposed change as set out in Parts A and B of this Addendum.

General

12. The proposed changes do not alter the overall policy approach in the Plan. The majority of the amendments are to reflect factual and typographical changes and to add clarity to policies which have been highlighted through representations received at Publication stage and by officers.

Minerals (PC50-PC53)

- 13. The change to Policy M06 Landbanks for Crushed Rock provides clarity on the time period that the policy applies over for the separate landbank for Magnesian Limestone. This will be throughout the plan period. The change to the supporting text corrects a factual error.
- 14. The changes to the supporting text in relation to silica sand clarifies the current situation in the other two minerals planning authorities in England with reserves for silica sand and provides an update on the realignment of the A59.

Hydrocarbons (oil and gas) (PC03-PC06, PC54-PC81)

15. As the majority of the representations received were in relation to the hydrocarbon section of the Plan, the number of changes proposed to this section is quite extensive. The changes initiated by the LPAs in Part A of the Addendum of Proposed Changes are just to correct typological errors. The proposed changes in Part B in response to representations are more significant. The proposed changes to the background section relate to the process, regulatory regime and definitions related to hydrocarbons.

Background text

- 16. On the whole, these are to clarify what the processes are, for example by changing 'drilling' to 'activity' clarifies that it is aspects of unconventional gas development other than drilling which may mean that development activity takes place over longer periods of time. In addition, the changes provide clarity as to the expected nature of development such as level of activity at different stages of development, the fact that the production stage of development may involve the re-fracturing of existing wells.
- 17. The changes in relation to the regulatory regime text are to clarify what the specific roles are for the Minerals Planning Authorities, Environment Agency, Health and Safety Executive, Department for Business, Energy and Industrial Strategy (formerly DECC) so it is clear who has responsibility for the different aspects of hydrocarbon development.
- 18. Changes to the definitions section reflect more accurately the distinctions between the development activity associated with conventional and unconventional hydrocarbon resources. Further definitions are provided in the glossary. Conventional hydrocarbons are oil and gas where the reservoir is in porous rock such as sandstone or limestone and can be extracted using traditional drilling techniques. Unconventional hydrocarbons refer to the type of oil and gas that cannot be extracted using traditional drilling techniques and include underground coal gasification, coal bed and coal mine methane and shale gas.

Policy M16

19. The changes to the supporting text to Policy M16 reflect the latest Government position

- (the original text referred to a consultation document which has now been introduced as policy). The implications of this change will mean that additional restrictions will be applied to operations using more than 1,000 cubic metres of fluid.
- 20. Text has been added which highlights that the minerals planning authorities are not seeking to unreasonably restrict activity typically associated with the production of conventional resources. In practice this will mean that well-established industries will not suddenly be subject to much tighter restrictions.

Policy M17

- 21. The proposed change to Policy M17 which seeks to replace 'planned' with 'permitted' in the context of the status of well pads that the policy applies to. 'Planned' could be interpreted in different ways and leaves the policy open to uncertainty whereas 'permitted' clearly means those well pads with planning permission (either implemented or not).
- 22. A proposed change has been made which recognises the potential impacts on air quality as a result of increased vehicle movements in relation to hydrocarbon development.
- 23. The remaining changes to the supporting text of M17 more accurately reflect the direction of national policy, guidance and available evidence.

Policy M18

- 24. The proposed change to policy M18 which removes the need to decommission wells that are to be suspended pending further hydrocarbon development is in line with the relevant regulatory requirements which state that wells which have reached the end of their operational phase should be decommissioned.
- 25. The change to the text in reference to water returned to the surface via a borehole has been amended to reflect that water arising on site may not always constitute waste. In practice this will mean that operators will need to have in place methods of testing the content of water arising on site and methods for dealing with genuine waste water as well as other water arising on site.

Potash and salt supply (PC07 - PC11, PC82)

26. Changes have been made to policy headings to relate to potash (in its general form) and rock salt rather than referencing polyhalite as there are other forms of potash. Amendments have then been made to the supporting text to define these different forms of potash which is considered necessary as there are different policy requirements depending on the form of potash and the national need for the mineral. Also each form of potash requires different levels of infrastructure requirements and as such it is important to make these distinctions.

Waste (PC12-PC14, PC83)

27. The proposed change to policy W11 1) recognises that it will be acceptable in principle to site new waste management facilities next to existing waste management sites where it can be demonstrated that co-locational benefits would arise. This is in line with the direction of policy W10 which sets out the overall locational principles for the provision of waste capacity.

Transport and Infrastructure (PC15-PC16, PC86-PC88)

28. The proposed change to policy I02 is to clarify that the whole policy applies to City of York not just part 2.

Safeguarding polices (PC17-PC19, PC84-PC88)

29. Proposed changes to Policy S01 and the supporting text clarify the status of the potash and polyhalite areas. Other additional text in the safeguarding section recognises that a pragmatic approach needs to be taken when implementing safeguarding requirements where an overlap with other types of proposed development occurs and emphasises that minerals and waste transport infrastructure is also safeguarded in the Plan.

Development Management Policies (PC20-PC23, PC89-PC97)

- 30. Many of the proposed changes are to correct typographical errors, provide clarity or more closely reflect the requirements of national policy. Several of the policies have more specific reasons for the proposed changes.
- 31. The proposed change to supporting text to Policy D03 is to reflect the potential for vehicles movements to impact on air quality. The proposed change to the supporting text for Policy D04 is to further clarify the purposes of the AONB designation. The proposed change to the supporting text of Policy D06 is included to reflect the presence of other potentially relevant designations in District local plans and to ensure appropriate links are made. The proposed change to the text in Policy D12 is to provide further flexibility in the policy recognising that all soils could make some contribution to ecological connectivity or carbon storage.

Site Allocations (Appendix 1) (PC24-PC26, PC98-PC109)

- 32. The proposed changes to the key sensitivities for sites that are proposed for allocation are to reflect the potential significance of a constraint that has been identified through the site assessment process, such as the proximity of a site of nature conservation interest.
- 33. The changes to development management requirements and site area are a mix of seeking to reduce the potential harm to an identified asset (such as a listed building) and drawing attention to the potential opportunities that may arise through development of a site.

Safeguarded Sites (Appendix 2) (PC27-PC39, PC110-PC113)

34. The changes in Appendix 2 correct typographical errors, provide updated information and add an additional site.

Policies Map (PC41-PC42)

35. Proposed changes to the policies map are to correct an omission and to make the text consistent with the text in the Plan.

How to get involved

36. Representations submitted at this stage must only be made against the Addendum of Proposed Changes and on grounds of legal compliance or soundness (see below) and be supported with evidence to demonstrate why these tests have not been met. Any representations received will be considered by the inspector as part of the examination in public.

Legal Compliance

37. To be legally compliant the Joint Plan has to be prepared in accordance with the Duty to Cooperate and legal and procedural requirements including the 2011 Localism Act and Town and Country Planning (Local Planning) (England) Regulations 2012 (as amended).

Tests of Soundness

- 38. The National Planning Policy Framework states that a Local Plan should be:
 - Positively prepared the plan should be based on a strategy which seeks to meet objectively assessed development and infrastructure requirements, including unmet requirements from neighbouring authorities where it is reasonable to do so and consistent with achieving sustainable development;
 - Justified the plan should be the most appropriate strategy, when considered against the reasonable alternatives, based on proportionate evidence;
 - Effective the plan should be deliverable over its period and based on effective joint working on cross-boundary strategic priorities; and
 - Consistent with national policy the plan should enable the delivery of sustainable development in accordance with the policies in the Framework.
- 39. The Addendum of Proposed Changes and supporting documents, as well as full details of how to make representations on the Addendum, are available on our website:

 www.northyorks.gov.uk/mwconsult. Paper copies of the documents will be available to view at Council offices and libraries throughout North Yorkshire and the City of York.
- 40. We recommend that you use the response form provided as this will enable us to record your representations correctly, which is particularly important at this stage. All representations should relate to, and include within the response, a Proposed Change (PC) number to ensure the representation is recorded against the correct text.
- 41. You can send us your completed response form either by post to:

Minerals and Waste Joint Plan Team Planning Services Business and Environmental Services North Yorkshire County Council County Hall, Northallerton DL7 8AH

Or by email to: mwjointplan@northyorks.gov.uk

42. The closing date for representations is 5pm on 6th September 2017.

43. PLEASE NOTE THAT WE ARE UNABLE TO ACCEPT REPRESENTATIONS RECEIVED AFTER THE DEADLINE.

44. If you would like to speak to someone about the Addendum of Proposed Changes please contact us using the contact details below:

North Yorkshire County Council: Tel: 01609 780780

City of York Council: Tel: 01904 552255

North York Moors National Park Authority: Tel: 01439 772700

Addendum of Proposed Changes to Publication Draft of the Minerals and Waste Joint Plan

Key

Example: New Text
Example: Deleted Text

Example: Text in bold is Policy wording

Part A - Proposed changes initiated by the Local Planning Authorities

PC	Page	Policy Ref/Paragraph	Change proposed	Reason
No.	Number	Number/Reference		
		point		
PC01	2,3	Sub-heading 'About this	Delete sub-heading About this Document and all subsequent text on pages	To reflect the closure of the
		Document'	2 and 3.	publication phase of the Plan
PC02	25	Para. 2.54 16 th line	were publis <u>ih</u> ed by	To correct a typographical error
PC03	78	Para. 5.108 2 nd line	Please note that the references to 'DECC' in Figure 13 should now be read as references to DBEIS as its successor	To correct a typographical error
PC04	84	Policy M16 d) i) 3 rd line	the policies map or is are otherwise considered	To correct a typographical error
PC05	86	Para. 5.121 5 th sentence	reference to their special qualities can be found in the relevant	To correct a typographical error
			m <u>M</u> anagement Plan for the area.	
PC06	87	Para. 5.125 5 th Sentence	This includes the need to take account of any Impact Risk Zones identified	To correct a typographical error
			by Natural England for SACs, SPAs, Ramsar sites and SSSSIs, via the requirements	
PC07	102	Potash, Polyhalite and Salt Section	Replace section heading Potash, Polyhalite and Salt with Potash and Salt	For consistency with proposed modifications to paras. 5.171 and 5.172
PC08	102	Para 5.171	Replace current para. 5.171	To clarify terminology relevant to
			"There are various forms of potassium bearing minerals which can be	potash and salt mineral resources
			mined for potash including sylvinite, polyhalite and carnalite. Potash is	

	1	_		
			mainly used as a fertiliser. Rock salt may occur in association with	
			potash and is commonly used for de-icing roads. Both potash and salt	
			occur at substantial depths below the eastern part of the plan area,	
			where existing extraction takes place. Identified resources lie mainly	
			beneath the North York Moors National Park."	
			with:	
			Potash is the generic term for potassium bearing minerals and has an	
			important economic value for fertiliser. Within the Plan area it takes the	
			form of sylvinite, which can be processed to create 'muriate of potash',	
			and polyhalite, which although lower in terms of potassium content, also	
			includes other important plant nutrients, particularly sulphur. Rock salt	
			may occur in association with potash and is commonly used for de-icing	
			roads. Both potash and salt occur at substantial depths below the eastern	
			part of the Plan area, where existing extraction takes place. Identified	
			resources lie mainly beneath the North York Moors National Park.	
PC09	102	Policy M22 1 st para. 1 st	Revise first line: Proposals for the extraction of potash, and salt or	To clarify terminology relevant to
		line	polyhalite from new sites	potash and salt mineral resources
PC10	102	Policy M22 2 nd para. 2 nd	Revise second line: Proposals for new surface development and	To clarify terminology relevant to
		line	infrastructure associated with the existing permitted potash, polyhalite	potash and salt mineral resources
			and salt mine sites in the National Park,	
PC11	103	Para 5.172	Replace current para. 5.172	To clarify terminology relevant to
			Potash is identified as a mineral of local and national importance in the	potash and salt mineral resources
			NPPF, which requires policies to be included for its extraction. There is	
			however no requirement within national policy to maintain a certain level	
			of potash reserves. Potentially viable and accessible resources of potash	
			are understood to lie mainly beneath the North York Moors National Park.	
			Where proposals for new potash (including polyhalite) mining activities are	
			located within the National Park they will need to be considered in	
			accordance with the requirements of the major development test (Policy	
			D04). This includes extensions to the operating period or renewal	
			applications for the existing mine sites at Boulby and Doves Nest Farm.	

			For these reasons it is not considered appropriate to allocate proposed sites in the Joint Plan but to consider any new proposals against the policy requirements set out above. with: In planning terms, the differentiation between the two forms of potash is important, in relation to the policy requirements of the major development test relating to need assessment. There is an existing national requirement for the sylvinite form of potash, whereas polyhalite is new to the global fertiliser market and is not yet an established product. Planning permission for Boulby Mine allows for the extraction of 'potash', covering both sylvinite and polyhalite (and also rock salt), whereas the 2015 permission for Sirius Minerals at Doves Nest is restricted to polyhalite only. Another important distinction is the fact that sylvinite requires processing and therefore has significant additional infrastructure requirements, whereas when polyhalite is mined the entire ore is used	
			with only the need for granulation. In Policy M22, the term 'potash' means all forms of the mineral unless where otherwise explicitly stated.	
PC12	115	Policy W02 4)	where they would be in line with the requirements of Policies W10 and W11.	To correct a typographical error
PC13	121	Policy W03 2)	with the site locational and identification principles in Polices Policies W10 and W11 will be permitted.	To correct a typographical error
PC14	135	Para. 6.94 last sentence	under Policies W10 and W11 and other relevant policies policies in the Joint Plan as appropriate.	To correct a typographical error
PC15	145	Para. 7.12 3 rd Sentence	constitute permitted development under the Town and Country Planning (General Permitted Development) (England) 2015 Order 1995 (as amended).	To update sentence to refer to the current legislation
PC16	146	Policy I02 2)	In addition, within the City of York area, development of ancillary minerals infrastructure will also only be permitted provided the following criteria are met:	To clarify the meaning of the policy.
PC17	149	Policy S01	Potash and (including polyhalite) resources within the Boulby Mine	To clarify the status of the

		1 st paragraph of Part 2)	licensed permitted area	relevant area
PC18	151	Para. 8.17 6 th line Para. 8.30 3 rd line	Revise 3 rd sentence:However, it would be appropriate to safeguard reserves and resources within the area licensed for extraction from that part of the Boulby Mine permission area indicated on the Policies Map (the only active potash mine in the Plan area), along with those resources forming part of the York Potash project that have been identified with a higher degree of confidence (i.e. the indicated and inferred resources). This will due, for example, to noise, dust, odour or	To clarify the status of the relevant area To correct a typographical error
PC20	166	Policy D04 Final sentence of final paragraph of Part 1)	Revise final sentence of final paragraph of Part 1): Appropriate and practicable compensation will be required for any avoidable unavoidable effects which cannot be mitigated.	To correct a typographical error
PC21	175	Para. 9.53 5 th line	Revise sentence:the development of enhanced ecological networks to improve reliance resilience and help to	To correct a typographical error
PC22	178	Para. 9.63	Add a return at end of paragraph to distinguish from para. 9.64	To improve presentation of the document
PC23	188	Key links to other relevant policies and objectives	Strategic Policies in Chapter 5, 6 and 7 and Policies D07, D09, D10, D13	To correct a typographical error
PC24	194	Text following Para. 10.1	Delete: Note: when providing a response relating to a specific site please ensure the site reference number is included with the relevant comments.	To reflect the closure of the publication phase of the Plan
PC25	30, 45, 82, 85 and 89 of Appendix 1	Reasons for allocating site	supply of aggregates (Policy M01) and the provision of crushed road rock (Policies M05 and M06) and could contribute to	To correct a typographical error on these 5 pages
PC26	137 and 144 of Appendix	'Submitted by' row	Revise: Stephenson & Son (on behalf of Mr W-R-Smith E Wilkin)	To correct a factual error on these 2 pages

	1			
PC27	159 of Appendix 2	Safeguarded Waste Site Contents list	Insert new safeguarded waste transfer (non-hazardous) site into table: Showfield Lane, Malton Revise waste facility type description for Knapton Quarry to: Composting, transfer, treatment and recycling	Consequential change arising from response to consultation
PC28	159 of Appendix 2	Waste Site Name column at start of Appendix 2	Revise Unit 8, Marsden Marston Business Park Genta Environmental, Marsden Marston Business Park Tofts Road, Kirkby Kirby Misperton Dalkia Bio Energy Ltd Stobart Group Burnistion Burniston Caucklands Caulklands/Thornton-le-Dale	To correct typographical errors and an operator name change
PC29	169 of Appendix 2	Site Name on Plan	Unit 8 Marsdon Moor Marston Business Park, Tockwith	To correct a typographical error
PC30	170 of Appendix 2	Site Name on Plan	Genta Environmental, Marsdon Moor Marston Business Park, Tockwith	To correct a typographical error
PC31	182 of Appendix 2	Page 182	Delete page 182 and re-number following pages	To remove a duplicate of the plan already shown on page 181
PC32	198 of Appendix 2	Site Name on Plan	Stonefall, Weatherby Wetherby Road, Harrogate	To correct a typographical error
PC33	201 of	Boundary of safeguarded	Revise boundary to reflect allocated area WJP17	For consistency

	Appendix 2	site for Skipton HWRC		
PC34	209 of Appendix 2	In Site Name column	Dalkia waste siteStobart Group	To update an operator name change
PC35	226 of Appendix 2	Site name on Plan	Whirtby Whitby Port	To correct a typographical error
PC36	227 of Appendix 2	Site name on Plan	Queens Staithe	To correct a typographical error
PC37	229 of Appendix 2	In Site Name column	Outgang Lane, Oswaldkirk Osbaldwick Ricall Riccall Airfield	To correct typographical errors
PC38	249 of Appendix 2	Site name on Plan	Outgang Lane, Oswaldkirk Osbaldwick	To correct a typographical error
PC39	257 of Appendix 2	Site name on Plan	Ricall Riccall Airfield	To correct a typographical error
PC40	264 of Appendix 3	Indicator 5 'Action Required if Trigger Point hit' column:	Review of provision of crushed rock site allocations if i8f necessary	To correct a typographical error
PC41	Policies Map	Мар	Include Areas of Search polygons on the policies map	To correct an omission
PC42	Policies Map	Мар Кеу	Revise references in Key to potash or polyhalite in the supporting justification to potash and salt	For consistency with the text of the Plan

Part B - Proposed changes in response to representations

PM No.	Page	Policy Ref/Paragraph	Change proposed	Reason
	Number	Number/Reference		
		point		
PC43	18	Para. 2.26 2 rd line	Revise para:	To reflect consistence with
			The NPPF also places emphasis upon conserving important landscape	national policy
			and heritage assets by requiring that landbanks of non-energy minerals	
			are, as far as is practical, provided outside National Parks, AONBs	
PC44	18	Para. 2.26 4 th sentence	Revise para:	To clarify the national policy
			The NPPF advises that in considering planning applications substantial	context relating to Green Belt.
			weight should be given to any harm to the Green Belt but inappropriate	
			development is by definition harmful to the Green Belt and should not	
			be approved except in very special circumstances. It also advises that	
			minerals extraction is not considered to be inappropriate development	
			within the Green Belt, provided the development it preserves openness	
			and would not conflict with the purposes of including land within it.	
			Harm to assets, including landscape and heritage assets, relevant to the	
			purpose of Green Belt designation equate to harm to the purposes of	
			Green Belt designation. Green Belt policy This is addressed further	
PC45	25	Para. 2.54 16 th line	Revise para:	To correct a factual error
			Plan period. Marine Plans for the East Inshore and East Offshore areas,	
			covering the area south of Flamborough Head, were published by DEFRA	
			the Marine Management Organisation in April 2014. These recognise	
PC46	25	Para. 2.54	Add new sentence at end of Para. 2.54: For the area north of	To clarify the status of marine
			Flamborough Head, and pending finalisation of a North East Marine Plan,	planning in the area
			reference should be made to the national Marine Policy Statement,	
			which also highlights the importance of marine aggregates in supplying	
			the construction industry.	
PC47	29	Para. 2.68 last sentence	Revise last sentence of para. 2.68: These imports, other than clear glass	To clarify the specific position

			grade silica sand, are thought to relate	relating to silica sand
PC48	33	Para. 2.88 2 nd bullet point	Revise 2 nd bullet point: Cross boundary supply issues relating to silica	To more closely align the text
			sand, which is a mineral of national significance importance.	with national policy
PC49	46	Para. 4.11 3 rd bullet point,	Add additional text to end of 3 rd bullet point, part c): in the Plan area	To further clarify where review
		part c)	or other significant regulatory changes relevant to the development of	may be required
			local planning policy	
PC50	55	Policy M06 1 st para.	A minimum overall landbank of 10 years will be maintained for crushed	To clarify the proposed approach
			rock throughout the plan period. A separate minimum 10 year	
			landbank will be identified and maintained for Magnesian Limestone	
			crushed rock throughout the plan period.	
PC51	64	Para. 5.55 15 th line	East Coast Inshore and Offshore Marine Plans (DEFRA MMO 2014)	To correct a factual error
			should help	
PC52	68	Para. 5.68 4 th sentence	Revise 4 th sentence: Neither of Sites within the other two MPAs in	To more closely align the text
			England with reserves of silica sand currently has do not have a 10 year	with national policy
			<u>landbank</u> as required by the NPPF national policy, although both are	
PC53	68	Para. 5.72	Replace existing para. 5.72	To reflect the evolving situation
			A further relevant consideration in respect of Blubberhouses Quarry is	in relation to proposals for
			that the Local Transport Plan for North Yorkshire has identified the need	realignment of the A59 near
			to realign the A59 road at Kex Gill, near Blubberhouses Quarry, to avoid	Blubberhouses
			recurring issues of land instability. A definitive proposed realignment is	
			not yet available and there is no safeguarded route. However, there is	
			potential for this project to overlap with the Blubberhouses quarry site.	
			In this scenario there would be a need to ensure that the potential for	
			conflict between the road alignment and the quarry is reflected in the	
			design of both schemes and the potential for any cumulative impacts	
			taken into account where necsaary.	
			201	
			with:	
			A further relevant consideration in respect of Blubberhouses Quarry is	
			that the County Council (within its Local Transport Plan 4: strategy and	
	I	1	the state of the s	I .

r				
			strategic transport prospectus) and the York and North Yorkshire & East	
			Riding Local Enterprise Partnerships (within its strategic economic plan)	
			have identified the need to realign the A59 road at Kex Gill, near	
			Blubberhouses quarry, as a key strategic priority. The existing alignment	
			of the A59 in the Kex Gill area is subject to poor land stability issues,	
			resulting in several road closures taking place on this regionally	
			important strategic trans Pennine route over the past 15 years.	
			A definitive proposed realignment is not yet available and there is no	
			safeguarded route. Work is currently on going identifying options,	
			however there is potential for this project to overlap with the	
			Blubberhouses quarry site. In this scenario there would be a need to	
			ensure that the potential for conflict between road realignment and the	
			quarry is reflected in design of both schemes and the potential for any	
			cumulative impact taken into account where necessary.	
PC54	75	Para. 5.93 2 nd sentence	Revise 2 nd sentence: This is a highly relevant issue for the Plan area	To reflect the fact that PEDL
			following the announcement by Government in late 2015 of new oil and	licenses are now awarded by the
			gas exploration and development licences	Oil and Gas Authority
PC55	75	Para. 5.94 1 st sentence	Revise 1 st sentence: The Government Oil and Gas Authority awards PEDLs	To reflect the fact that PEDL
				licenses are now awarded by the
				Oil and Gas Authority
PC56	78	Para. 5.107 1 st bullet	Revise last sentence of 1 st bullet point: For unconventional hydrocarbons,	To clarify that it is aspects of
			exploratory drilling activity may take considerably longer, especially	unconventional gas development
				other than drilling which may
				mean that development activity
				takes place over longer periods
PC57	78	Para. 5.107 3 rd bullet	Revise last sentence of 3 rd bullet point: The production stage <u>may involve</u>	To clarify the expected nature of
			re-fracturing of existing wells and is likely to require the periodic	development at production stage
			maintenance of wells, which may require use of drilling equipment.	
PC58	80	Para. 5111	Add new text at end of para. 5.111:	To provide further clarification of
I			appropriately located. <u>Hydrocarbon development typically involves</u>	the expected nature of
			appropriately located. <u>Hydrocarb</u> on development typically involves	The expected nature of

			development. Depending on the nature of the development, it is likely	forward
			that there will generally be a lesser degree of activity during any	
			production phase.	
PC59	81	Para. 5.112	Add new text after end of 5 th sentence:	To clarify the important
			health and safety. The Environment Agency has an important	regulatory role of the
			regulatory role in relation to the management of returned water and	Environment Agency in this
			Naturally Occurring Radioactive Materials (NORM). In accordance with	matter
PC60	81	Para. 5.116 2 nd line	Replace reference to DBEIS in 2 nd line with Oil and Gas Authority	To correct a factual inaccuracy
PC61	83	Para. 5.118	Revise para. 5.118: Planning guidance and case law makes clear that	To more closely align the text
			Minerals Planning Authorities do not need to carry out their own	with national policy and guidance
			assessments of potential impacts which are controlled by other	
			regulatory bodies. focus on the control of processes or emissions	
			themselves where these are subject to approval under pollution control	
			<u>regimes.</u> It states that they can determine planning applications having	
			considered the advice of those the relevant regulatory bodies without	
			having to wait for other approval processes to be concluded.	
PC62	83	Para. 5.119	Revise para. 5.119 d): 'Conventional hydrocarbons' include oil and gas	To clarify the distinctions
			found within geological 'reservoirs' with relatively high	between development activity
			porosity/permeability, extracted using conventional drilling and	associated with conventional and
			production techniques .	unconventional resources
			Revise para. 5.119 e): 'Unconventional hydrocarbons' include	
			hydrocarbons such as coal bed and coal mine methane and shale gas,	
			extracted using unconventional techniques, including hydraulic fracturing	
			in the case of shale gas, as well as the exploitation of in-situ coal seams	
			through underground coal gasification.	
			Revise para. 5.119 g): In planning terms it is considered that relevant	
			distinctions can be drawn between the specific nature and/or scale of	
			activities associated with certain stages of development for conventional	
			hydrocarbons and those used for unconventional hydrocarbons. These	
			differences may include the potential requirement for a larger number of	
			well pads and individual wells, the volume and pressures of fluids used	

			for any hydraulic fracturing processes and the specific requirements for	
			any related plant and equipment and the management of related wastes.	
			important to distinguish between:	
			i)—The use of unconventional techniques to extract hydrocarbons	
			such as hydraulic fracturing, underground gasification and coal	
			bed methane extraction; and	
			The use of more conventional, less complex drilling and production	
			techniques to extract hydrocarbons	
PC63	86	Para. 5.122	ii) Revise para. 5.122: While the Infrastructure Act 2015 and	To more accurately reflect the
1 603	80	Faia. 3.122	secondary legislation address hydraulic fracturing which occurs	current regulatory position
			underground, the Government has also consulted on introduced	relating to the Government's
			further restrictions, in the form of a prohibition on high-volume	Surface Protections for hydraulic
			· · · · · · · · · · · · · · · · · · ·	,
			hydraulic fracturing operations from taking place being carried out	fracturing
			from new or existing wells that are drilled at the surface in	
			specified protected areas , although they are not yet in force . As	
			proposed The restrictions would will principally affect apply to	
			surface development for unconventional hydrocarbons involving	
			high volume hydraulic fracturing that is used for the carrying out	
			of "associated hydraulic fracturing" the definition of which is	
			contained in section 4B(1) of the Petroleum Act 1998. The	
			Government has stated that, in addition, these restrictions will	
			apply where an operator is required to get consent from the	
			Secretary of State for hydraulic fracturing that is not "associated	
			hydraulic fracturing", and that the Secretary of State intends to	
			require that such consent be obtained for operations which use	
			more than 1,000 cubic metres of fluid at any single stage, or	
			expected stage, unless an operator can persuasively demonstrate	
			why requiring such consent would not be appropriate in their	
			<u>case.</u> The areas proposed for protection protected through this	
			means are National Parks, AONBs, World Heritage Sites,	
			Groundwater Source Protection Zone 1, SSSIs, Natura 2000 sites	

PC64	86	Para. 5.123 3 rd sentence	(SPAs and SACs) and Ramsar sites. Although these areas all benefit from strong national policy protection in their own right, the proposed restrictions would do not, in themselves, constitute planning policy as they would will be implemented though the oil and gas licensing regime. Furthermore, whilst the proposed surface restrictions would will provide	To more accurately reflect the current regulatory position relating to the Government's Surface Protections for hydraulic
PC65	86	Para. 5.124 1 st sentence	An additional consideration is that the new Regulations and proposed surface protections restrictions would will only apply to	fracturing To more accurately reflect the current regulatory position relating to the Government's Surface Protections for hydraulic fracturing
PC66	86	Para. 5.124	Revise last sentence of para. 5.124 and add new text at end: Similarly, it is considered that where hydraulic fracturing is proposed for the purposes of supporting the production of conventional gas resources, there is potential for this to give rise to a generally similar range of issues and potential impacts, although it is acknowledged that fracturing for stimulation of conventional gas production would be likely to involve generally lower volumes and/or pressures. In these circumstances it is therefore appropriate that such development is subject to the same policy approach. However, it is not the intention of the Mineral Planning Authorities to unreasonably restrict activity typically associated with production of conventional resources, which is a well-established industry in the Plan area and they will therefore apply the policy accordingly and reasonably based on the specific circumstances of the proposal under consideration this should be subject to the same policy approach that is applied to hydraulic fracturing for unconventional gas, as the range of issues and potential impacts are likely to be similar.	To clarify the intended approach and ensure appropriate flexibility in the Plan

PC67	87	Para. 5.127 15 th line	Revise 7 th sentence: Such equipment may only be present on site for	To reflect the potential position
			relatively short periods, or potentially a number of months, or	
			intermittently over a period of years at established well pads where	
			successive wells are drilled or refracturing of existing wells takes place.	
PC68	88	Para. 5.130	Add new text at end of para. 5.130: In some parts of the Plan area	To reflect the presence of other
			affected by PEDLs, areas of locally important landscapes have been	potentially relevant designations
			identified in District and Borough local plans. Where these continue to	in district local plans and to
			form part of the statutory development plan, and are relevant to a	ensure that appropriate links are
			proposal which falls to be determined by North Yorkshire County Council	made
			as Minerals and Waste Planning Authority, regard will be had to the	
			requirements of any associated local plan policy.	
PC69	88	Footnote 16	Revise text of footnote 16: For the purposes of interpreting this and	To further clarify the intended
			other Policies in the Pplan, the term 'local communities' includes	approach
			residential areas as well as residential institutions such as	
PC70	89	Policy M17 2) ii) a)	Revise text: The proximity of a proposed new well pad site to other	To clarify the proposed approach
			existing, planned <u>permitted</u> or unrestored well pads,	
PC71	91	Para. 5.131 9 th line	Insert new sentence after ' movements.': Vehicle movements also	To reflect the potential for
			have the potential to impact on air quality, particularly in locations	vehicle movements to impact on
			where Air Quality Management Areas have been identified and this will	air quality
			also be a relevant consideration in identifying suitable traffic routes, via a	
			<u>Transport Assessment.</u> It is therefore	
PC72	92	Para 5.137	Revise 1 st sentence and add new sentence between 1 st and 2 nd	To clarify the approach to
			sentences: To give an indication at this stage, however, it is considered	preventing unacceptable
			unlikely that proposals which would lead to a total development density,	cumulative impact
			including operational and restored sites, of more than 10 well pads per	
			100km ² PEDL area (pro-rata for PEDLs of less than 100km²) would be	
			compatible with the purpose of this element of the policy. Where an	
			area being developed by an operator comprises a PEDL or licence block	
			area of less, or more, than 100km ² the density guideline will be applied	
			pro-rata.	
PC73	92	Para 5.137 7 th line	Revise 2 nd sentence: For PEDLs located in the Green Belt or where a	To clarify the approach to

		relatively high concentration of other land use constraints exist, including	preventing unacceptable
		, ,	cumulative impact
		appropriate.	'
93	Para. 5.143	Revise 1 st sentence: Whilst oil and gas hydrocarbon development has the	For consistency
		potential	
94	Para. 5.147	Revise text to state: In considering appropriate noise limits at sensitive	To improve consistency with
		receptors, operators will as a minimum be expected to meet the	national policy and guidance
		suggested required limits set out in the NPPF and national Planning	
		Practice Guidance, with the objective of ensuring a high standard of	
94	Para. 5.148 3 rd sentence		To more accurately reflect the
		induced are likely to be of very low magnitude, it It will be important to	available evidence
		ensure that development which could give rise to induced seismicity is	
		,	
94	Para. 5.149		To clarify that these issues may
		•	also be relevant to other forms of
			hydrocarbon development
95	Para. 5.151	•	To correct a factual inaccuracy
96	Policy M18 2) i)	· · · · · · · · · · · · · · · · · · ·	To more accurately reflect the
		• • •	relevant regulatory requirements
			relating to decommissioning of
		, · · · · · · · · · · · · · · · · · · ·	wells
		·	
96	Para. 5.153	· · · · · · · · · · · · · · · · · · ·	To clarify that water arising on
		, , ,	site may not always constitute
		,	waste
		surface via a borehole.	
		Revise 4 th sentence: Water constituting waste and requiring	
		management as waste Such waste can arise in substantial volumes and	
	94 94 94 95	94 Para. 5.147 94 Para. 5.148 3 rd sentence 94 Para. 5.149 95 Para. 5.151 96 Policy M18 2) i)	Para. 5.143 Revise 1 st sentence: Whilst oil and gas hydrocarbon development has the potential Para. 5.147 Revise text to state: In considering appropriate noise limits at sensitive receptors, operators will as a minimum be expected to meet the suggested required limits set out in the NPPF and national Planning Practice Guidance, with the objective of ensuring a high standard of protection for local amenity. Site lighting Para. 5.148 3 rd sentence Although evidence suggests that any earth tremors that could be induced are likely to be of very low magnitude, it! will be important to ensure that development which could give rise to induced seismicity is located in areas of suitable geology. Para. 5.149 Revise 1 st sentence: The potential for emissions to water or air is also a key issue, particularly for proposals involving hydraulic fracturing hydrocarbon development. Policy M18 2) i) Revise 1 st sentence in 2 nd sentence to DBEIS with Oil and Gas Authority. Revise text of 2) part i): Following completion of the operational phase of development, or where wells are to be suspended pending further hydrocarbon development, any wells will be decommissioned so as to prevent the risk of any contamination of ground and surface waters and emissions to air; and Para. 5.153 Revise 1 st sentence: A significant issue with hydrocarbon development, particularly development involving hydraulic fracturing, is the need to manage the various forms of waste water that may be returned to the surface via a borehole. Revise 4 th sentence: Water constituting waste and requiring

			other contaminants.	
PC81	97	Para. 5.156 16 th line	Revise text: potentially leading to very small scale induced seismic	To clarify the position
			activity (earth tremors). Proposals for this	
PC82	102	Policy M22 2 nd para.	Add new sentence at end of 2 nd paragraph: the development.	To clarify the proposed policy
			Proposals for new surface development and infrastructure which are	approach in relation to proposals
			considered to represent major development will be assessed against	which are considered to
			the criteria for major development set out in Policy D04.	represent major development
PC83	140	Policy W11 parts 1), 2), 3)	Revise text of part 1) to:	To improve consistency of the
		and 5)	1) Siting facilities for the preparation for the re-use, recycling, transfer	policy with Policy W10
			and treatment of waste (excluding energy recovery or open	
			composting) on previously developed land, industrial and	
			employment land, or at <u>or adjacent to</u> existing waste management	
			sites	
			Make equivalent changes to parts 2), 3) and 5)	
PC84	154	Policy S03 key links to	Add reference in key links: W10	To clarify this important link
		other policies and	·	
		objectives		
PC85	155	Para. 8.30	Revise Para. 8.30 by inserting new text at end of paragraph: <u>It is</u>	To emphasise the need for a
			acknowledged that in some cases, including at the former mine sites in	pragmatic approach to
			the Plan area, there are other extant proposals for redevelopment which	implementing safeguarding
			are matters for determination by the relevant local planning authority	requirements
			and that such proposals could overlap with land proposed for	
			safeguarding in the Joint Plan. In these circumstances the Minerals and	
			Waste Planning Authority will seek to work constructively with the	
			relevant local planning authority and developers to ensure that a	
			proportionate approach to implementing safeguarding of minerals and	
			waste infrastructure requirements is taken.	
PC86	156	Para.8.33	Add new text at end of Para. 8.33: <u>It is recognised that rail transport</u>	To emphasise the need for a
			<u>infrastructure at former mine sites in the Plan area are important for</u>	pragmatic approach to
			their potential to serve other existing or proposed rail-linked uses. It is	implementing safeguarding

	<u> </u>		T
			requirements
		approach to implementing safeguarding of minerals and waste	
		<u>infrastructure requirements is taken.</u>	
156	Para. 8.34	Add new sentence at end of Para. 8.34: The East Coast marine Plan	To emphasise the linkage
		(Policy PS3) supports the protection and expansion of port and harbour	between marine and terrestrial
		capacity.	planning
159	Para. 8.47 Safeguarding	Revise 11 th bullet point: Applications for development on land which is	To reflect the fact that minerals
	exemption criteria list	already allocated in an adopted local plan where the plan took account	and waste transport
		of minerals, and waste and minerals and waste transport infrastructure	infrastructure is also safeguarded
		safeguarding requirements	in the plan
164	Para. 9.16	Revise final sentence: Vehicle movements can have a range of impacts,	To reflect the potential for
		including cumulative impacts, such as on local amenity and in some cases	vehicle movements to impact on
		•	air quality
		affected, particularly in locations where Air Quality Management Areas	
		have been identified and other development management policies in the	
		Joint Plan will therefore be relevant in some circumstances.	
165	Para. 9.21	Add new text after the end of para. 9.21: The primary purpose of AONB	To further clarify the purposes of
		designation is to conserve and enhance natural beauty. In pursuing the	AONB designation
		primary purpose of designation, account should be taken of the needs of	
		promoting sustainable forms of social and economic development that in	
		themselves conserve and enhance the environment. Recreation is not an	
		far as this is consistent with the conservation of natural beauty and the	
	159	159 Para. 8.47 Safeguarding exemption criteria list 164 Para. 9.16	Infrastructure requirements is taken.

			needs of agriculture, forestry and other uses.	
PC91	171	Para. 9.42	Add new sentence at end of Para. 9.42: In some parts of the Plan area,	To reflect the presence of other
			areas of locally important landscapes have been identified in other local	potentially relevant designations
			plans. Where these continue to form part of the statutory development	in district local plans and to
			plan, and are relevant to a proposal which falls to be determined by the	ensure that appropriate links are
			relevant minerals and waste planning authority, regard will be had to the	made.
			requirements of any associated local plan policy.	
PC92	167	Policy D05 part 1)	Proposals for minerals development within the York and West	To more closely reflect the
			Yorkshire Green Belts will be supported where it would be consistent	requirements of national policy
			with the purposes of Green Belt identified in national policy and	
			preserve the openness of the Green Belt and, where the proposed	
			development would be is located within the York Green Belt, it would	
			preserve the historic character and setting of York.	
PC93	168	Policy D05 part 2) 2 nd	Substantial weight will be given to any harm to the Green Belt and	To more closely reflect the
		paragraph	inappropriate waste development in the Green Belt will only be	requirements of national policy
			permitted in very special circumstances , which must <u>will need to</u> be	
			demonstrated by the applicant in which the harm by reason of	
			inappropriateness, or any other harm, is clearly outweighed by other	
			considerations. order to outweigh harm caused by inappropriateness,	
			or any other harm.	
PC94	179	Policy D09 3) 2 nd sentence	Revise 2 nd sentence to read: Development which would lead to an	To correct a typographical error
			unacceptable risk of, or be at an unacceptable risk from, all sources of	
			flooding (i.e. surface and groundwater flooding and groundwater	
			flooding from rivers and coastal waters) will not be permitted.	
PC95	183	Policy D10 1) i)	Replace existing text of D10 1) i) with: Applicants are encouraged to	To more closely reflect the
			discuss proposals at an early stage with local communities and other	requirements of national policy
			relevant stakeholders and where practicable reflect the outcome of	
			those discussions in submitted schemes.	
PC96	184	Policy D10 Part 2) viii)	Revise to read: Promoting the delivery of Achieving significant net gains	To clarify the proposed approach
			for biodiversity and the establishment of a which help create coherent	and reflect the diminishing

			and resilient ecological networks, based on contributing. Where	significance of biodiversity action
			practicable, towards established objectives including the creation of	plans
			Biodiversity Action Plan habitats proposals should contribute	
			significantly to the creation of habitats of particular importance in the	
			<u>local landscape</u> and seeking to delivering benefits at a landscape scale.	
			This includes wet grasslands and fen in the Swale and Ure valleys and	
			species-rich grassland on the Magnesian limestone ridge.	
PC97	190	Policy D12 2 nd paragraph,	Revise 2 nd sentence: Development which would disturb or damage soils	To provide further flexibility in
		2 nd sentence	of high environmental value, such as intact peat or other soil	the policy recognising that all
			contributing to ecological connectivity or carbon storage, will not be	soils could make some
			permitted.	contribution to ecological
				connectivity or carbon storage.
PC98	17 of	MJP06 Development	Insert new bullet point: Applications should be supported by a	To adequately reflect the
	Appendix	requirements criteria	comprehensive archaeological assessment	significance of heritage assets at
	1			this site
PC99	21 of	MJP07 Development	Insert new bullet point: Applications should be supported by a	To adequately reflect the
	Appendix	requirements criteria	comprehensive archaeological assessment	significance of heritage assets at
	1			this site
			Revise final bullet point: An appropriate restoration scheme using	
			opportunities for habitat creation and reconnecting the henges to their	
			landscape setting, but which is also appropriate to location within a	
			birdstrike safeguarding zone	
PC100	25 of	MJP33 Development	Revise 5 th bullet point: Appropriate site design to ensure protection of	To reflect the proximity of the
	Appendix	requirements criteria	the aquifer and the River Swale which lies immediately adjacent to the	site to the River Swale
	1		<u>site</u>	
PC101	34 of	MJP21 Development	Revise last bullet point: An appropriate restoration scheme using	To recognise the opportunities
	Appendix	requirements criteria	opportunities for habitat creation and connectivity, but which is also	arising at this site
	1		appropriate to location within a birdstrike safeguarding zone	
PC102	35 of	MJP21 Site Plan	Revise site boundary of allocation MJP21 to exclude land nearest to the	To reduce the harm to the setting
	Appendix		Killerby Hall Stable Block listed building	of the listed building
	1			

PC103	37 of	MJP17 Development	Revise last bullet point: An appropriate restoration scheme using	To recognise the opportunities
	Appendix	requirements criteria	opportunities for habitat creation and connectivity, but which is also	arising at this site
	1		appropriate to location within a birdstrike safeguarding zone	
PC104	39 of	MJP17 Site Plan	Revise site boundary of allocation MJP17 to exclude land nearest to Rudd	To reduce the harm to elements
	Appendix		Hall and Ghyll Hall listed buildings	which contribute to the
	1			significance of the listed buildings
PC105	70 of	WJP15 Development	Revise last bullet point: An appropriate restoration scheme using	To recognise the opportunities
	Appendix 1	requirements criteria	opportunities for habitat creation and connectivity	arising at this site
PC106	78 of	MJP55 Key sensitivities	Revise 1 st bullet point of Key Sensitivities to include York and Selby Cycle	To reflect that the potential
	Appendix	and Development	<u>Track SINC</u>	significance of this constraint
	1	requirements		
			Revise 1 st bullet point of Development Requirements to include <u>York and</u>	
			Selby Cycle Track SINC	
PC107	120 of	WJP06 Key sensitivities	Revise 1 st bullet point of Key Sensitivities to include <u>York and Selby Cycle</u>	To reflect that the potential
	Appendix	and Development	<u>Track SINC</u>	significance of this constraint
	1	requirements		
			Revise 1 st bullet point of Development Requirements to include <u>York and</u>	
20100	1.10	450	Selby Cycle Track SINC	- G
PC108	140 of	1 st Column text: Estimated	Revise this text to read: Estimated dDate of commencement	To reflect that the planning
	Appendix	date of commencement		permission for this development
DC100	140 of	2 nd Column tout relating to	Revise this text to read: By April 2017 (base on requirement for	has been implemented
PC109		2 nd Column text relating to date of commencement	implementation specified in decision notice for planning application	To reflect that the planning
	Appendix	date of commencement	12/03385/FULM) November 2016	permission for this development has been implemented
PC110	179 of	Southmoor Energy Centre	Revise plan to only show core site and principal access to the highway	To reflect the fact that there are
PCIIU	Appendix	safeguarded site	Revise plan to only show core site and principal access to the highway	proposals for other development
	2	salegualueu site		on the former Kellingley Colliery
	-			site
PC111	186 of	Knapton Quarry	Revise reference to facility type to: Composting, transfer, treatment and	To more accurately reflect the
	Appendix	safeguarded site	recycling	current role of the site

	2	Facility Type		
PC112	217 of	Kellingley Colliery	Revise plan by deleting area of safeguarded site that lies outside the Plan	To correct a factual error
	Appendix	safeguarding plan	area	
	2			
PC113	Appendix	Safeguarded waste sites	Insert new safeguarded waste transfer (non-hazardous) site: Showfield	To reflect the significant role
	2		Lane, Malton	currently played by this site in the
				Ryedale area

Contact us Minerals and Waste Joint Plan Team Planning Services, North Yorkshire County Council, County Hall, Northallerton, North Yorkshire, DL7 8AH

Email: mwjointplan@northyorks.gov.uk

Tel: **01609 780780**